

August 17, 2023



Bid #2024-01

McGee Outdoor Classroom

Addendum #2

1. Would drilled and epoxy anchor bolts be allowed instead of cast in place?

YES, THIS IS ALLOWABLE.

2. Concrete piers left over from the portable class rooms can be seen in spots. Would you want a per cubic yard or per pier price for removal and disposal?

PLEASE PROVIDE A PER PIER PRICE FOR REMOVAL AND DISPOSAL.

3. Any required materials or compaction testing?

YES, COMPACTION TESTING IS REQUIRED.

4. The print has a 0.0 for top of slab. Does that have an associated elevation and benchmark? Do we have an existing structure that needs to be matched? Or does the contractor choose the best height for the slab?

CONTRACTOR SHOULD CHOOSE THE BEST HEIGHT FOR THE SLAB AND PROVIDE THAT INFORMATION TO AI ENGINEERS FOR REVIEW.

5. Concrete notes on fifth room page 2 of 6 contradict general site plan page 1 of 1 for reinforcement, concrete mix, depth of concrete, and finish. If the depth of the concrete slab is 8" the footing / Pier detail on page 2 of 6 will also be inaccurate.

NOTED. WE WILL REVIEW AND PROVIDE A CORRECTION.